

# APPROVAL SHEET FOR SUSPENDED LOAD OPERATIONS

SLO-KSC-1991-008

TITLE Orbiter Towing Operations

DOCUMENT NUMBER/TITLE OMI US112,50026

PREPARED BY M. Glenn

DATE 7/5/01

**REQUIRED APPROVAL**

CONTRACTOR       DESIGN                       R & QA                       OPERATIONS                       SAFETY

NASA                       DESIGN                       R & QA                       OPERATIONS                       SAFETY

TYPE OR PRINT NAME	SIGNATURE	ORGN.	DATE
M. Glenn	<i>M. Glenn</i>	PH-P1	7/5/01
R. Summers	<i>R. Summers</i>	PH-H1	7/5/01
Glenn Roberts	<i>Glenn Roberts</i>	USA 5173 0145	7-5-01
John W. Garnett	<i>John W. Garnett</i>	USA 5451	7-5-01 1-6035
D. R. Clarkson	<i>D. R. Clarkson</i>	USA SAFETY Eng	7-5-01
R. E. Harvey	<i>Richard Harvey</i>	USA 5450	7-6-01

CONTRACTOR DIRECTOR OF SAFETY

**NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)**

**SLO-KSC-1991-008  
CHANGE 2, JULY 2001  
PAGE 1 OF 4**

**OPERATION:** Orbiter Towing Operations

**SUPPORTING DOCUMENTS:** The associated operational procedure/systems assurance analyses are as follows:

1. OMI V5112.007, Orbiter Tow Operations - OPF to MDD.
2. OMI V5112.008, Orbiter Tow Operations - VAB HB-2 to MDD.
3. OMI V5112.009, Orbiter Tow Operations - MDD to OPF.
4. OMI V5112.013, Orbiter Tow Operations - VAB Transfer Aisle to MDD.
5. OMI V5112.014, Orbiter Tow Operations - MDD to VAB HB-2.
6. OMI V5112.015, Orbiter Tow Operations - MDD to VAB Transfer Aisle.
7. OMI S0026, Shuttle Landing – Post Landing Convoy Operations - EAFB
8. SAA290M01-001, Systems Assurance Analysis for the 55 Ton Main Hoists, Access Service Platform Hoists and the Wind Restraint Mechanism on the Mate/Demate Device at the Shuttle Landing Facility - KSC (SLF) and SLS-1 (DFRC).

**GENERAL DESCRIPTION:** These operations involve the towing of the Orbiter to and from the Mate/Demate Device (MDD) at the Shuttle Landing Facility (SLF), Kennedy Space Center and SLS-1, DFRC. The Orbiter is either towed to the Orbiter Processing Facility (OPF) or the Vehicle Assembly Building (VAB) to be readied for its next flight or towed to the MDD for ferry flight.

A detailed engineering review and hazards analysis of this operation have been conducted. This work has resulted in hardware and/or procedure modifications that minimize the exposure of employees to working under suspended loads. Due to the uniqueness of the activity and the limitations imposed when using present systems, hardware, and facilities, there remain some tasks where suspended load operations are required under specifically approved and controlled conditions. The Orbiter tow to and from the MDD requires a minimum number of personnel under the load to perform the following task:

1. Orbiter tow/spot into/out of the MDD apron passing under the suspended H70-0743 Orbiter Ferry Flight lifting sling (3 personnel-20 minutes).

**RATIONALE/ANALYSIS:** The suspended load tasks comply with the NASA Alternate Safety Standard for Suspended Load Operations as follows:

**Alternate Standard Requirement #1a:** Orbiter towing/spotting into and out of the MDD cannot be conducted without personnel beneath the suspended load. The tasks performed under the load have been analyzed and evaluated with the determination no feasible engineering design or procedural options are readily available to eliminate the suspended load operation. Redesign options of the

**NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)**

**SLO-KSC-1991-008  
CHANGE 2, JULY 2001  
PAGE 2 OF 4**

MDD were suggested to allow hard points at particular levels. The design options added uncertainty whether the hard points would be able to be disengaged properly from the Orbiter, which would affect the safety and integrity of the Orbiter. In addition, these design alternatives would pose other risks for personnel working at heights.

**Alternate Standard Requirement #1b:** Secondary support systems to assume support of (catch) the load were evaluated and were not feasible for this operation. Design criteria was too cumbersome to prevent the Orbiter and sling from being a suspended load and also prevented access to areas of critical work that needed to be performed.

**Alternate Standard Requirement #1c:** The number of personnel allowed under the suspended load for each task is as stated in the General Description. These personnel are also identified with safety vests to annotate the required personnel for the operation.

**Alternate Standard Requirement #1d:** Personnel will accomplish the required suspended load tasks as quickly and safely as possible to minimize time exposure; see General Description.

**Alternate Standard Requirement #2:** Suspended load operations are reviewed and approved on a case-by-case/specific need basis - see General Description and Alternate Standard Requirement #1.

**Alternate Standard Requirement #3:** Only those suspended load operations approved by the NASA Safety and Mission Assurance Division Chief will be permitted. A list of approved suspended load operations will be maintained by the NASA Safety and Mission Assurance Division.

**Alternate Standard Requirement #4:** OMI's V5112.XXX and S0026 are written to allow only required personnel under the suspended load. These OMI's are available on site for inspection during the operation.

**Alternate Standard Requirement #5:** A new suspended load operation not covered by this SLOAA, deemed necessary due to unusual or unforeseen circumstances where real time action is required, shall be documented and approved by the NASA Safety and Mission Assurance Division Chief.

**Alternate Standard Requirement #6:** The three 55 ton hoists at the MDD are designed, tested, inspected, maintained, and operated in accordance with the NASA Safety Standard for Lifting Devices and Equipment, NSS/GO-1740.9. The hoists are designed to a minimum safety factor of 5 (based on the ultimate yield

**NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)**

**SLO-KSC-1991-008  
CHANGE 2, JULY 2001  
PAGE 3 OF 4**

strength) for the hoist load-bearing components. The H70-0743 Orbiter Ferry Flight lifting sling is designed with a safety factor of 5 against ultimate strength and a safety factor of 3 against yield.

The hoists are equipped with two holding brakes and an emergency overspeed brake, each capable of holding the hoist rated capacity.

The hoists were one-time proofloaded at 125 percent of rated capacity, are load tested annually at 100 percent of rated capacity, and have a quarterly, semiannual and annual preventive maintenance program to ensure proper operation.

The wire rope is inspected monthly for discrepancies. Nondestructive testing of the hoist hooks is performed annually.

When performing the towing operation, one hoist is connected to the forward attach point of the H70-0743 Orbiter Ferry Flight lifting sling and two hoists are connected to the aft attach points. The Orbiter Ferry Flight lifting sling weighs approximately 26,000 and the attached wind restraint tubes weigh approximately 25,000 pounds. The three hoists simultaneously lift a maximum load of approximately 145 tons, which is within their rated capacity.

**Alternate Standard Requirement #7:** A System Assurance Analysis (SAA) has been completed on the 55 ton hoists at the MDD. The SAA includes a Failure Modes and Effects Analysis/Critical Item List (FMEA/CIL) and a hazard analysis (see Supporting Documents). The SAA identifies no single failure points for the MDD 55 ton hoists.

**Alternate Standard Requirement #8:** Visual inspections for cracks or other signs of damage or anomalies are performed on the hoist hooks and lifting sling assembly along with crane functional checks prior to each operation per NSS/GO-1740.9.

**Alternate Standard Requirement #9:** The hoist operators, Emergency (E) stop operators, and mechanical technicians are all trained and have current certifications. Operators will remain at the hoist controls while personnel are under the load.

**Alternate Standard Requirement #10:** Appropriate control areas are established and maintained prior to and during the operation. Only required personnel (man loaded in the procedure) are permitted in this area.

**NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)**

**SLO-KSC-1991-008  
CHANGE 2, JULY 2001  
PAGE 4 OF 4**

**Alternate Standard Requirement #11:** Personnel are briefed just prior to performing the task about the hazard involving the suspended load. A pretask briefing and a safety walkdown of the area are conducted prior to the lift to ensure all systems and personnel are ready to support. All participants are instructed on their specific tasks and warned of the hazards involved. Following any crew change, new personnel are instructed by the task leader on their specific tasks and warned of the hazards involved.

**Alternate Standard Requirement #12:** Personnel beneath the suspended load will be in radio, visual, or voice contact with the hoist controller and/or signal person. Upon loss of communication, the operation shall stop immediately, personnel shall clear the hazardous area, and the load shall be safed. Operations shall not continue until communications are restored.


**Alternate Standard Requirement #13:** Ground controllers and E-stop operators are properly positioned during all phases of the lifting operation in full view of the load block, lifting fixtures and fixture attach points. One E-stop operator, remote from the hoist operator, can stop the hoist if a failure indication is observed. Personnel working beneath the load shall remain in continuous sight of the operator and/or signal person.

**Alternate Standard Requirement #14:** The NASA Safety and Mission Assurance Division shall conduct periodic reviews to ensure the continued safety of suspended load procedures.

**Alternate Standard Requirement #15:** The NASA Safety and Mission Assurance Division will provide copies of approved SLOAAs, a list of approved suspended load operations, a list of cranes/hoists used for suspended load operations and copies of the associated FMEA/CIL and hazards analyses to NASA Headquarters.

APPROVAL:

DATE:

   
\_\_\_\_\_  
William C. Higgins  
Chief, Safety and Mission Assurance Division  
Kennedy Space Center