

# APPROVAL SHEET FOR SUSPENDED LOAD OPERATIONS

SLO-KSC-1991-009

TITLE Solid Rocket Motor Destack Operations Using  
250-Ton Crane

DOCUMENT NUMBER/TITLE OMI B5141, SRB Destack

PREPARED BY Malcolm Glenn

DATE 2/18/99

## REQUIRED APPROVAL

CONTRACTOR	<input type="checkbox"/> DESIGN	<input type="checkbox"/> R & QA	<input type="checkbox"/> OPERATIONS	<input type="checkbox"/> SAFETY
NASA	<input type="checkbox"/> DESIGN	<input type="checkbox"/> R & QA	<input type="checkbox"/> OPERATIONS	<input type="checkbox"/> SAFETY

TYPE OR PRINT NAME	SIGNATURE	ORGN.	DATE
Malcolm Glenn	<i>Malcolm Glenn</i>	EI-C-A	2/18/99
LLOYD EDGECOMB	<i>Lloyd Edgecomb</i>	USA 5532	3/17/99
WALTER BOYTER	<i>Walter C. Boyter</i>	PK-H	4/20/99
J. W. GARRETT	<i>John W. Garrett</i>	USA 5451	4/28/99
A. M. STEVENS	<i>AM Stevens</i>	USA 5450	4/30/99

CONTRACTOR DIRECTOR OF SAFETY



**NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)**

**SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 1 OF 12**

**OPERATION:** Solid Rocket Motor Destack Operations Using 250-Ton Crane

**SUPPORTING DOCUMENTS:** The associated operational procedure/systems assurance analyses are as follows:

1. OMI B5141, SRB Destack.
2. SAA09FY12-005, System Assurance Analysis of the 250-Ton Bridge Cranes at the Vehicle Assembly Building (VAB).

**GENERAL DESCRIPTION:** A maximum of six personnel are required to be directly under the suspended solid rocket motor segment to support destacking operations.

- Remove the V-2 volume filler from tang capture feature.
- Remove o-ring from tang capture feature o-ring groove.
- Remove corrosion and/or contaminants from clevis and tang.
- Apply grease to tang and clevis bare metal.
- Remove o-rings from clevis o-ring grooves (2 each).
- Walk-down the field joint following segment demate.

The Redesigned Solid Rocket Motor (RSRM) segment is connected to the H77-0384-3 lifting beam in the high bay. The lifting beam is connected to the 250-ton Delmar Hydra-set which is connected to the 250-ton bridge crane. The hydra-set is specifically used in this task to perform a demate of the RSRM segments.

The segment is depinned, demated, and raised 18 inches for inspection and removal of the o-rings, V-2 volume filler removal, and inspection for corrosion and obvious defects. These operations require personnel to be under a suspended load. After these inspections are complete the segment is repositioned to the Suspended Load Abatement Plan (SLAP) stand in the transfer aisle for inspections of the tang metal part mating surfaces, and tang j-seal cleaning. The SLAP stand is used to abate suspended load hazard during transfer aisle inspections. The segment is then lifted and positioned on the segment transportation pallet. There are no personnel under the segment during segment positioning over the transportation pallet. The segment is held stationary until personnel can man-up on the pallet. The segment is then positioned on the pallet.

**RATIONALE/ANALYSIS:** The suspended load tasks comply with the NASA Alternate Safety Standard for Suspended Load Operations as follows:



NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)

SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 2 OF 12

**Alternate Standard Requirement #1a:** The operation cannot be performed without personnel beneath the suspended load because there are no operational or design means of performing the segment destacking operation without risking damage to flight hardware or compromising the integrity of the field joint. By allowing personnel to position their hands and arms under the segment, there is verification the field joint was properly assembled and that all components were thoroughly inspected during installation. Design options evaluated to abate the suspended load increased the hazards associated with working under a suspended segment.

The addition of new tooling in the high bay will increase the everyday hazards associated with stacking operations. The additional tooling will increase the stacking time line (hence exposed propellant hazards) and potential for personal injury. Presently, the following tooling is required to mate a segment:

Temposonics - a computer record of the mating segment's rate of engagement and parallelism. The device consists of four sensor rods, connected by cables to a data acquisition system (DAS) and computer.

Field Joint Assembly Fixture (FJAF) - tooling designed to ensure proper clearances for the capture feature o-ring groove by "bear hugging" the outboard clevis leg. This reduces the likelihood of the barrier o-ring from being cut during assembly. This piece of tooling is built in four 8-foot sections that rest on the clevis leg. Each piece is placed on the outer clevis leg by a minimum of two personnel.

Lifting Beam Console - provides real-time display to assist engineering in monitoring destacking progress.

Hydra-set Console - console controls the 250-ton hydra-set used to perform the demating operations.

Should an incident occur, such as a propellant fire, the tooling used to prevent a segment from dropping in the event of a failure would add an additional obstacle in the event emergency egress is warranted. Additional tooling would also add to the everyday hazards associated with working on elevated platforms and increase potential tripping hazards.

Two design options were evaluated to abate the suspended load operation. One was to modify the access platforms and/or the entire high bay to support the 330,000 pounds segments during the destacking operations. This did not seem



NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)

SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 3 OF 12

physically possible without completely redesigning the VAB and no guarantees could be made that the destacking operation's critical processes would not be affected. The access platforms are not able to support the weight of a segment. A complete redesign of VAB High Bay 1 and 3 would be required.

The other option would be to develop tooling that would interface with the tang and the clevis of the two segments being mated/demated. However, back-up support of some unknown design concept could not be envisioned to maintain the dropped hardware in the vertical position. This option is not desirable as the integrity of the field joint would be greatly compromised.

**Alternate Standard Requirement #1b:** Secondary support systems to assume support of (catch) the load were evaluated and were not feasible for this operation; see Alternate Standard Requirement #1a.

**Alternate Standard Requirement #1c:** The maximum number of personnel directly under the suspended segment destacking operations is six.

**Alternate Standard Requirement #1d:** Personnel will accomplish the required suspended load tasks as quickly and safely as possible to minimize time exposure. Total exposure time is approximately 4 to 8 hours to complete all the preparation, inspection, and removal operations.

**Alternate Standard Requirement #2:** Suspended load operations are reviewed and approved on a case-by-case/specific need basis - see General Description and Alternate Standard Requirement #1.

**Alternate Standard Requirement #3:** Only those suspended load operations approved by the Center NASA Safety Assurance Director will be permitted. A list of approved suspended load operations will be maintained by the Center NASA Safety Assurance Directorate.

**Alternate Standard Requirement #4:** OMI B5141 is written to allow only required personnel under the suspended load. The OMI is available on site during the operation.

**Alternate Standard Requirement #5:** A new suspended load operation not covered by this SLOAA, deemed necessary due to unusual or unforeseen circumstances where real time action is required, shall be documented and approved by the Center NASA Safety Assurance Director.



NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)

SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 4 OF 12

**Alternate Standard Requirement #6:** Suspended load operations in the VAB associated with lifting motor segments involve the use of one of the 250-ton bridge cranes. The 250-ton bridge cranes are designed, tested, inspected, maintained, and operated in accordance with NSS/GO-1740.9, the NASA Safety Standard for Lifting Devices and Equipment. The cranes are designed with a minimum safety factor of 5 (based on the ultimate material strength) for the hoist load bearing components.

The cranes are equipped with redundant hoist drive systems (including hoist wire ropes and holding brakes) each capable of lifting and holding the load to the crane's rated capacity. The cranes have a dual braking system with overspeed braking. A load test is performed annually to 100 percent of the rated capacity of the crane.

The 250-ton bridge cranes undergo a monthly, quarterly, semiannual, and annual preventive maintenance program. The wire rope is inspected monthly for discrepancies. The crane hook undergoes an annual Non-Destructive Testing (NDT) inspection.

The H77-0384-3 segment lifting beams were one-time proofloaded to 740,000 +/- 74,000 pounds and are load tested annually to 462,000 +/- 10,000 pounds. The beams also undergo a semiannual preventive maintenance and an annual NDT for load-bearing members and critical welds.

The lifting beams were designed to a 5 to 1 safety factor for failure and 3 to 1 for yield. The safe working load of the H77-0384-3 lifting beam is 370,000 pounds. The heaviest flight component lifted is the aft booster which weighs approximately 350,000 pounds.

The Delmar DHS 250 (vendor part number 16553) is a 250-ton hydra-set used for stacking booster motor segments. The hydra-set underwent a one-time proof test of 1,000,000 +/- 10,000 pounds for a minimum of 5 minutes. The 250-ton hydra-set also undergoes an annual load test of 625,000 pounds. A preventive maintenance program and a leak check are performed prior to the start of each flight motor set stacking operation. Prior to each use the hydra-set undergoes an operational check.

**Alternate Standard Requirement #7:** A System Assurance Analysis (SAA) has been completed on the VAB 250-ton bridge cranes. The SAA includes a Failure Modes and Effects Analysis/Critical Item List (FMEA/CIL) and a hazard analysis (see Supporting Documents).



NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)

SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 5 OF 12

The SAA identifies single failure points (SFP) (11 for the 250-ton crane) in the main hoist system when the hoist is lifting or lowering. Failure of the motor-generator set (one each) or the main hoist motors (two each) would allow the load to lower without regenerative braking at approximately 10 feet/minute (2 inches/second). Failure of the remaining SFPs would allow the load to lower with regenerative braking at approximately 0.25 feet/minute (0.05 inches/second). There are no SFPs when the hoist is static.

There is no history of failure with the SFPs in the critical failure mode. The use of high quality, reliable components and a comprehensive maintenance, inspection, and test program, including preoperational checks ensures that the crane systems operate properly. If a failure were to occur, it can be recognized by a brake set light, ammeter, or selsyn position indicator (depending on the failure) which are in view of both operators. The crane operators would secure the load by applying the brakes.

Emergency (E) stop operators, remote from the crane operator's cab, can stop the crane if a failure indication is observed.

The associated SAA CIL sheets identify the rationale for accepting the risk of the SFPs, including design information, failure history, and the operational controls in effect to minimize the risks (maintenance, inspection, test, etc.).

**Alternate Standard Requirement #8:** The 250-ton bridge crane undergoes a visual inspection and pre-operational checkout prior to each use per NSS/GO-1740.9.

**Alternate Standard Requirement #9:** A trained, licensed and certified operator will remain at the controls while personnel are under a suspended load. In addition, a qualified Emergency Stop operator is stationed in the vicinity of personnel working under the suspended load. All personnel responsible for the direction and/or performance of the operation undergo training that meets or exceeds the required certifications per NSS/GO-1740.9.

**Alternate Standard Requirement #10:** Control areas are established per OMI B5141. For solid rocket booster lifting operations, a control area is established in the high bay and adjacent transfer aisle. Only essential personnel are allowed in the control area. A second, smaller control area is established under a suspended load.



NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)

SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 6 OF 12

Control areas are established using rope, amber lights, and placards to ensure non-essential personnel are kept out of the area. For operations under a suspended load, a badge board is maintained in the immediate area. Only those personnel badged and with the approval of the Task Leader are allowed under the load.

**Alternate Standard Requirement #11:** Pre-operational briefings are held by the Task Leader and all essential personnel involved with the operation. Shift change pre-operational briefings are held if operations are to occur on multiple shifts.

**Alternate Standard Requirement #12:** Communications (by voice, radio and visual) are maintained with all personnel under a suspended load. Emergency procedures contain instructions and personnel are trained to discontinue operations if communications are lost. The hardware is safed and the area is cleared if additional hazards warrant clearing the control area. All personnel are cleared from under a suspended load during loss of communications.

**Alternate Standard Requirement #13:** All personnel remain within sight of the Lift Coordinator and the Emergency Stop operator.

**Alternate Standard Requirement #14:** The Center NASA Safety Assurance Directorate shall conduct periodic reviews to ensure the continued safety of suspended load procedures.

**Alternate Standard Requirement #15:** The Center NASA Safety Assurance Directorate will provide copies of approved SLOAAs, a list of approved suspended load operations, a list of cranes/hoists used for suspended load operations and copies of the associated FMEA/CIL and hazards analyses to NASA Headquarters.



**NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)**

**SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 7 OF 12**

**OPERATION:** Aft Booster Set Down on the Aft Booster Transportation Pallet Post Ball Fittings Using 250-Ton Crane

**SUPPORTING DOCUMENTS:** The associated operational procedure/systems assurance analyses are as follows:

1. OMI B5141, SRB Destack.
2. SAA09FY12-005, System Assurance Analysis of the 250-Ton Bridge Cranes at the Vehicle Assembly Building (VAB).

**GENERAL DESCRIPTION:** Four personnel are required to be directly under the suspended aft booster assembly during aft booster positioning on the aft booster transportation pallet posts. Operations include the following:

- Clean, inspect, and repair the aft skirt shoe sockets.
- Align aft skirt shoes during set down operations.

The aft booster is connected to the H77-0384-3 lifting beam. The lifting beam is connected to the 250-ton Delmar Hydra-set which is connected to the 250-ton bridge crane. The hydra-set is not specifically used in this task but is required for segment demate operations.

The aft booster is raised off the Mobile Launch Platform (MLP) hold down posts (HDP) for disassembly. The aft booster assembly is then lifted to the transfer aisle from the high bay. There are no personnel under the suspended aft booster during lifting operations to the transfer aisle. The aft booster is then positioned approximately 2 feet above the transportation pallet posts. The booster is held stationary until the personnel can man-up on the transportation pallet.

The aft booster shoe sockets are then inspected for missing dry-lube lubrication. The booster is then aligned and positioned on the posts of the pallet.

**RATIONALE/ANALYSIS:** The suspended load tasks comply with the NASA Alternate Safety Standard for Suspended Load Operations as follows:

**Alternate Standard Requirement #1a:** The operation cannot be performed without personnel beneath the suspended load because there are no operational means of performing the booster alignment without risking damage to flight hardware. By physically positioning a person under the aft booster, clearances required in the alignment are maintained. Design options to build an alignment



**NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)**

**SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 8 OF 12**

tool increased the hazards associated with working under a suspended aft booster segment. The alignment tool would introduce a new suspended load operation. The procedures have been modified to minimize the exposure time and number of personnel exposed to the suspended load hazard.

An inspection stand shoe adapter to perform inspections while supporting the aft booster assembly over the transportation pallet was investigated. The shoe adapter was determined to be unstable for protecting personnel under a suspended load. The adapter would have to be bolted to the support post ball fittings on the transportation pallet. The clearances required to prevent damage to the exit cone (approximately 6 feet above the floor of the transfer aisle to allow for nozzle clearance) prohibit the use of dunnage or any other stand. The proposed adapters, which would weigh a minimum of 400 lbs each, would require the assistance of a hoist or a mobile crane for installation on the transportation pallet. Installation of these adapters would be a suspended load operation.

No other tooling is available or feasible to support the weight of the entire aft booster assembly should a crane or lifting beam failure occur.

**Alternate Standard Requirement #1b:** Secondary support systems to assume support of (catch) the load were evaluated and were not feasible for this operation; see Alternate Standard Requirement #1a.

**Alternate Standard Requirement #1c:** The maximum number of personnel allowed under the suspended booster at any one time during aft booster alignment is four. One person is required under each post during the alignment operation.

The maximum number of personnel under the suspended booster at any one time during aft booster shoe inspection and dry-lube repair is four; at each shoe.

**Alternate Standard Requirement #1d:** Personnel will accomplish the required suspended load tasks as quickly and safely as possible to minimize time exposure. Total exposure time is approximately 30 minutes for alignment/positioning and 30 minutes per shoe for inspection and repair.

**Alternate Standard Requirement #2:** Suspended load operations are reviewed and approved on a case-by-case/specific need basis - see General Description and Alternate Standard Requirement #1.



NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)

SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 9 OF 12

**Alternate Standard Requirement #3:** Only those suspended load operations approved by the Center NASA Safety Assurance Director will be permitted. A list of approved suspended load operations will be maintained by the Center NASA Safety Assurance Directorate.

**Alternate Standard Requirement #4:** OMI B5141 is written to allow only required personnel under the suspended load. The OMI is available on site during the operation.

**Alternate Standard Requirement #5:** A new suspended load operation not covered by this SLOAA, deemed necessary due to unusual or unforeseen circumstances where real time action is required, shall be documented and approved by the Center NASA Safety Assurance Director.

**Alternate Standard Requirement #6:** Suspended load operations in the VAB associated with lifting motor segments involve the use of one of the 250-ton bridge cranes. The 250-ton bridge cranes are designed, tested, inspected, maintained, and operated in accordance with NSS/GO-1740.9, the NASA Safety Standard for Lifting Devices and Equipment. The cranes are designed with a minimum safety factor of 5 (based on the ultimate material strength) for the hoist load bearing components.

The cranes are equipped with redundant hoist drive systems (including hoist wire ropes and holding brakes) each capable of lifting and holding the load to the crane's rated capacity. The cranes have a dual braking system with overspeed braking. A load test is performed annually to 100 percent of the rated capacity of the crane.

The 250-ton bridge cranes undergo a monthly, quarterly, semiannual, and annual preventive maintenance program. The wire rope is inspected monthly for discrepancies. The crane hook undergoes an annual Non-Destructive Testing (NDT) inspection.

The H77-0384-3 segment lifting beams were one-time proofloaded to 740,000 +/- 74,000 pounds and are load tested annually to 462,000 +/- 10,000 pounds. The beams also undergo a semiannual preventive maintenance and an annual NDT for load-bearing members and critical welds.

The lifting beams were designed to a 5 to 1 safety factor for failure and 3 to 1 for yield. The safe working load of the H77-0384-3 lifting beam is 370,000 pounds.



NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)

SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 10 OF 12

The heaviest flight component lifted is the aft booster which weighs approximately 350,000 pounds.

The Delmar DHS 250 (vendor part number 16553) is a 250-ton hydra-set used for stacking booster motor segments. The hydra-set underwent a one-time proof test of 1,000,000 +/- 10,000 pounds for a minimum of 5 minutes. The 250-ton hydra-set also undergoes an annual load test of 625,000 pounds. A preventive maintenance program and a leak check are performed prior to the start of each flight motor set stacking operation. Prior to each use the hydra-set undergoes an operational check.

**Alternate Standard Requirement #7:** A System Assurance Analysis (SAA) has been completed on the VAB 250-ton bridge cranes. The SAA includes a Failure Modes and Effects Analysis/Critical Item List (FMEA/CIL) and a hazard analysis (see Supporting Documents).

The SAA identifies single failure points (SFP) (11 for the 250-ton crane) in the main hoist system when the hoist is lifting or lowering. Failure of the motor-generator set (one each) or the main hoist motors (two each) would allow the load to lower without regenerative braking at approximately 10 feet/minute (2 inches/second). Failure of the remaining SFPs would allow the load to lower with regenerative braking at approximately 0.25 feet/minute (0.05 inches/second). There are no SFPs when the hoist is static.

There is no history of failure with the SFPs in the critical failure mode. The use of high quality, reliable components and a comprehensive maintenance, inspection, and test program, including preoperational checks ensures that the crane systems operate properly. If a failure were to occur, it can be recognized by a brake set light, ammeter, or selsyn position indicator (depending on the failure) which are in view of both operators. The crane operators would secure the load by applying the brakes.

Emergency (E) stop operators, remote from the crane operator's cab, can stop the crane if a failure indication is observed.

The associated SAA CIL sheets identify the rationale for accepting the risk of the SFPs, including design information, failure history, and the operational controls in effect to minimize the risks (maintenance, inspection, test, etc.).



NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)

SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 11 OF 12

**Alternate Standard Requirement #8:** The 250-ton bridge crane undergoes a visual inspection and pre-operational checkout prior to each use per NSS/GO-1740.9.

**Alternate Standard Requirement #9:** A trained, licensed and certified operator will remain at the controls while personnel are under a suspended load. In addition, a qualified Emergency Stop operator is stationed in the vicinity of personnel working under the suspended load. All personnel responsible for the direction and/or performance of the operation undergo training that meets or exceeds the required certifications per NSS/GO-1740.9.

**Alternate Standard Requirement #10:** Control areas are established per OMI B5141. For solid rocket booster lifting operations, a control area is established in the high bay and adjacent transfer aisle. Only essential personnel are allowed in the control area. A second, smaller control area is established under a suspended load.

Control areas are established using rope, amber lights, and placards to ensure non-essential personnel are kept out of the area. For operations under a suspended load, a badge board is maintained in the immediate area. Only those personnel badged and with the approval of the Task Leader are allowed under the load.

**Alternate Standard Requirement #11:** Pre-operational briefings are held by the Task Leader and all essential personnel involved with the operation. Shift change pre-operational briefings are held if operations are to occur on multiple shifts.

**Alternate Standard Requirement #12:** Communications (by voice, radio and visual) are maintained with all personnel under a suspended load. Emergency procedures contain instructions and personnel are trained to discontinue operations if communications are lost. The hardware is safed and the area is cleared if additional hazards warrant clearing the control area. All personnel are cleared from under a suspended load during loss of communications.

**Alternate Standard Requirement #13:** All personnel remain within sight of the Lift Coordinator and the Emergency Stop operator.

**Alternate Standard Requirement #14:** The Center NASA Safety Assurance Directorate shall conduct periodic reviews to ensure the continued safety of suspended load procedures.



NASA SUSPENDED LOAD OPERATION  
ANALYSIS/APPROVAL (SLOAA)

SLO-KSC-1991-009  
CHANGE 1, FEBRUARY 1999  
PAGE 12 OF 12

**Alternate Standard Requirement #15:** The Center NASA Safety Assurance Directorate will provide copies of approved SLOAAs, a list of approved suspended load operations, a list of cranes/hoists used for suspended load operations and copies of the associated FMEA/CIL and hazards analyses to NASA Headquarters.

APPROVAL:

DATE:

Malcolm Glenn for 4/28/99  
Bruce L. Jansen  
Acting Director, Safety Assurance  
Kennedy Space Center